

CFMS CONSULTING INC.

PROJECT PROFILE



G & G Partnership Architects

SUNNYBROOK HEALTH SCIENCES CENTRE 'M WING' GROUND FLOOR OR RENOVATIONS TORONTO, ONTARIO

Statistics:

Gross Floor Area

878 sm (9450 sf)

Construction Cost

Total \$3,250,000

Mechanical \$1,600,000

Reference

Sunnybrook HSC
Mr. Ian Kenny
Project Manager
416.480.6100

Completion Date

August 2007

The integration of three (3) new operating rooms and two (2) new 'PACU' areas within the Hospital's existing 'M Wing' facility.

HVAC systems include for:

- Constant volume, 100% OA, heat recovery unit for cooling of ORs / PACUs in summer and heating / humidification of same in winter
- OR / PACU air terminal units for reheating of supply air to maintain space temperature

Services provided by CFMS:

- Verification of DDC system & BAS
- Performance testing of HVAC systems
- Co-ordination of mechanical equipment and systems training
- Preparation and presentation of systems operating manual
- Seasonal performance testing of HVAC systems